

CITY OF NEWARK
Delaware

CONTRACT NO. 17-13

PURCHASE OF MATERIAL FOR THE CHEMOURS PROJECT

ADDENDUM NO. 1

December 21, 2017

Please change on page 33, 10, Construction - Internal Components, Cable Termination Compartments, Paragraph 3 as follows:

600-ampere rated bushing wells shall be designed to accept 600-ampere bushing inserts and shall have removable, silver-plated copper studs.

We would also like to add under Item #3 - Two (2) 35kV Underground Distribution Switchgear, an option Item #3A, as follows:

We would like an optional bid for Two (2) 35kV Underground Distribution Switchgear, **without** the Motor Operators, listed on page 22, under 11. Features.

Please add the following chart on page 37, Proposal, as follows:

BID PROPOSAL OF CONTRACT NO. 17-13 COMPANY _____					
ITEM	QUANTITY	DESCRIPTION	UNIT PRICE	DEL'Y ARO	MFG'S CATALOG #
1	2	34.5kV Vacuum Circuit Breaker			
2	3	3 Pole Gang Operated Switch			
3	2	35kV Underground Distribution Switchgear with the Motor Operators			
3A	2	35kV Underground Distribution Switchgear without the Motor Operators			
4	2	35kV PMDF Dead-front Padmounted Primary Metering Switchgear			